

BRUHAT BANGALORE MAHANAGARA PALIKE, YALAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92


DRAFT SCHEDULE-B

Name of Work : Detailed Estimate for the Improvements of roads in Munigurappa layout in ward 07, Byatarayanapura, Kodigehalli sub division.

Sl. No	Approved Quantity	Description	Unit	Sanctioned Rates	
				In Figures	In Words
1	1848.00 ✓	Removing BS Slab of drain and stacking.	Sqm	50.11 ✓	
2	1293.60 ✓	Refixing stone slabs of drains and pointing in CM 1:3.	Sqm	70.04 ✓	
3	554.40 ✓	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. (7.50cms thick)	Sqm	343.44 ✓	
4	736.00 ✓	KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after break	cum	65.88 ✓	
5	3680.00 ✓	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occurring during rolling including cost of all labour, HOM of machinery complete as per specifications. (167, I.No. 19.64) SR 2013-14	Sqm	4.05 ✓	
6	736.00 ✓	KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. (P. 166, Item No. 20.18)	cum	1121.04 ✓	
8	3680.00 ✓	KSRRB M500-6. Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. (P. 171,	Sqm	44.28 ✓	


Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

9	92.00	KSRRB M500-18. Providing and laying semi dense bituminous concrete 25 mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.8 complete in all respects as per specifications. with 80/100 grade bitumen using 40-60 HMP using mechanical paver (P. 174, Item No. 21.20.5	cum	9794.52	
10	25.92	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 (P. 5, I.No. 2.3) SR-2013-14	cum	151.74	
11	25.92	KSRB 4-1.2: Providing and laying in position plain cement concrete of 1 mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P. 12, I.No. 4.2) SR-2013-14	cum	4639.68	
12	11.52	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (P 16, I.No 4.28) SR-2013-14	Sqm	3588.84	
13	23.95	KProviding and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges)Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-3320Kg/cum) (P. 19, I.No. 4.49.1) SR-2013-14	Sqm	224.64	
14	6.62	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (P. 19, I.No. 4.46) SR-2013-14	cum	6675.48	


Executive Engineer
 Byatarayanapura Division
 Yelahanka Zone, B.B.M.P.
 Bangalore - 560 092

15	10.26	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (P. 19, I.No. 4.46) SR-2013-14	Qtl	7380.72	
16	9.60	KSRB 15.1.3 - do - Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P.119.I.No. 15.3) SR-2013-14	Sqm	79.92	
17	826.00	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. From 0.00 to 5.00 Km (Page No.141)	cum	72.71	

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL BBMP, Bangalore

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕರಡು ಬೆಂಡರ್ ಪಡೆಯಲ್ಪಟ್ಟು
ಶಿಫ್ಟಿಪಡೆಗಳ ಸಂಖ್ಯೆ.....()
ಶಿಫ್ಟಿಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

Chief Engineer
Yelahanka Zone
Bruhat Bangalore Mahanagara Palike
Bangalore 92